

**ROAD TRAFFIC ACT
(CHAPTER 276, SECTIONS 119 AND 140)**

ROAD TRAFFIC (TRAFFIC SIGNS) RULES

ARRANGEMENT OF RULES

Rule

1. Citation
 - 1A. Definitions
 2. Prescribed traffic signs
 3. Types of traffic signs
 4. Inscriptions on signs
 5. Change of directions
 6. Parking places
 7. Lines, markings or traffic devices on roads
 8. Bus lanes
 - 8A. Bicycle lane
 9. Road divider
 10. Light signals for vehicles
 11. The 3-colour system
 12. The 2-colour system
 13. Light signals for lanes
 14. Miniature light signals
 15. Light signals for cyclists, pedestrians and PMD riders
 16. Light signals for bicycles, etc.
 17. Temporary beacons
 18. Temporary signs for road works
 - The Schedule
-

[1st November 1991]

Citation

1. These Rules may be cited as the Road Traffic (Traffic Signs) Rules.

Definitions

1A. In these Rules, unless the context otherwise requires —

[Deleted by S 170/2024 wef 01/03/2024]

“cyclist” means an individual who is riding a bicycle, three-wheeled pedal cycle, recumbent device or power-assisted bicycle, but excludes an individual who is walking beside and pushing a bicycle, three-wheeled pedal cycle, recumbent device or power-assisted bicycle;

[S 170/2024 wef 01/03/2024]

“mobility scooter” and “wheeled toy” have the meanings given by section 2(1) of the Active Mobility Act 2017 (Act 3 of 2017);

“pedestrian” means —

- (a) an individual walking, with or without animals;
- (b) an individual in a non-motorised wheelchair;
- (c) an individual driving a motorised wheelchair or riding a mobility scooter;
- (d) an individual travelling on inline skates, roller-skates or a wheeled toy;
- (e) an individual pushing a pram, stroller or trolley, or a motorised or non-motorised wheelchair; or
- (f) an individual walking beside and pushing a bicycle, three-wheeled pedal cycle, recumbent device, power-assisted bicycle, personal mobility device or any other vehicle;

[S 170/2024 wef 01/03/2024]

[S 170/2024[Deleted by S 170/2024 wef 01/03/2024]]

“personal mobility device” or “PMD” means a personal mobility device other than a three-wheeled pedal cycle or recumbent device;

[S 170/2024 wef 01/03/2024]

“PMD rider” means an individual who is riding a personal mobility device on a road as permitted by section 5A(2) of the

Act, but excludes an individual who is walking beside and pushing a PMD;

[S 276/2018 wef 05/05/2018]

[S 170/2024 wef 01/03/2024]

“recumbent device” and “three-wheeled pedal cycle” have the meanings given by rule 2 of the Road Traffic (Bicycles, Three-wheeled Pedal Cycles, Trishaws and Recumbent Devices — Construction and Use) Rules 2024 (G.N. No. S 157/2024).

[S 170/2024 wef 01/03/2024]

Prescribed traffic signs

2.—(1) Subject to any directions which the Minister may give under section 119 of the Act, the traffic signs authorised to be drawn or placed on or near any road shall —

- (a) be at least of the size, and conform to the colour and type as prescribed in the diagrams set out in the Schedule; and
- (b) conform to the descriptions set out in these Rules.

(2) The dimension of the traffic signs as given in the diagrams set out in the Schedule denotes the dimension in millimetres unless otherwise stated.

(3) A traffic sign drawn or placed on or near a road shall be deemed to be a prescribed traffic sign and to have been so lawfully drawn or placed unless the contrary is proved.

(4) The fact that a traffic sign differs slightly in size, colour or type from that prescribed in these Rules shall not prevent the traffic sign from being a regular or lawful sign so long as the sign is not thereby misleading or its general appearance materially altered or its effectiveness impaired.

Types of traffic signs

3. The traffic signs set out in the Schedule are divided as follows:

- (a) regulatory signs as set out in Part I of the Schedule which are intended to inform road users of special obligations,

restrictions and prohibitions with which they must comply and are subdivided into —

- (i) mandatory signs;
 - (ii) priority signs; and
 - (iii) prohibitory or restrictive signs;
- (b) warning signs as set out in Part II of the Schedule which are intended to warn road users of the danger on the road and to inform them of the nature and source of the danger; and
- (c) informative signs as set out in Part III of the Schedule which are intended to provide road users with information which may be useful while they are travelling.

Inscriptions on signs

4. The inscription on the traffic signs shall be in the English language except that there may also be inscription in another language or languages on the signs.

Change of directions

5. The direction of any arrow or other indication on the signs shown in the diagrams in the Schedule may be reversed or otherwise varied as circumstances may require.

Parking places

6. The signs shown in diagrams 36 (a) to 36 (f) in Part I of the Schedule shall be used only in connection with parking places owned by or under the control of the Government or statutory bodies.

Lines, markings or traffic devices on roads

7.—(1) Lines, markings and other traffic devices may be drawn or placed on a road to indicate —

- (a) the position where vehicles shall stop or reduce speed when required to do so by a traffic sign, or a police officer engaged in the control of traffic;
- (b) the course and direction to be followed by traffic;

- (c) a street refuge;
- (d) places reserved for bus terminals, bus stops, taxi stands, taxi stops, P2P stops, trishaw stands, motor cycle parks, bicycle parks, car parks, coach parks, lorry parks, trailer parks, loading and unloading bays and vehicles of handicapped persons;

[S 883/2025 wef 01/01/2026]

- (e) a pedestrian crossing;
- (f) a bicycle crossing;
- (g) the edge of the road;
- (h) a central reservation which divides the road for the safety or guidance of traffic;
- (i) a yellow box;
- (j) a road shoulder along an expressway;
- (ja) a part-day bicycle lane;

[S 803/2022 wef 16/10/2022]

- (jb) a full-day bicycle lane;

[S 803/2022 wef 16/10/2022]

- (k) a part-day bus lane;

[S 639/2005 wef 03/10/2005]

- (ka) a full-day bus lane;

[S 639/2005 wef 03/10/2005]

- (kb) a bus-only lane;

[S 227/2026 wef 20/04/2026]

- (l) the section of the road where parking of vehicles is restricted or prohibited;
- (m) the boundary on the road which no vehicle, whether overtaking other vehicles or not, shall cross;

[S 651/2008 wef 20/12/2008]

- (n) a parking place or a public service vehicle stand;

[S 651/2008 wef 20/12/2008]

yellow lines each of not less than 300 mm in width and spaced not less than 3,000 mm apart from the centre to centre from one edge of the road to the other as shown in diagram 140(e) in Part III of the Schedule.

(7) A signalised bicycle crossing is indicated by 2 parallel white lines each of not less than 300 mm in width and spaced not less than 3,000 mm apart from the centre of one line to the other and with the 2 lines running from one edge of the road, subway or bridge, as the case may be, to the other as shown in diagram 145(a) in Part III of the Schedule.

(8) A yellow box is indicated by yellow lines connecting the 4 corners of an area of road at a road junction or on any part of the road as shown in diagrams 140(a) to 140(d) in Part III of the Schedule.

(9) A road shoulder is the strip constructed with a surface suitable for motor vehicles to move along or stop, along the left (nearside) or right (offside) of a road and is demarcated from the road by a continuous white marginal line of not less than 300 mm in width as shown in diagram 151(e) in Part III of the Schedule.

(10) The edge of a road is indicated by a continuous or broken white marginal line of not less than 300 mm in width as shown in diagrams 139(b) and 139(c) in Part III of the Schedule.

(11) A part-day bus lane is the section of a road marked by a longitudinal continuous yellow line of not less than 300 mm in width and transverse yellow lines of not less than 200 mm in width and 1,200 mm in length as shown in diagrams 115(a) to 115(d) in Part III of the Schedule.

[S 639/2005 wef 03/10/2005]

(11A) A full-day bus lane is the section of a road marked by —

- (a) a longitudinal continuous yellow line of not less than 300 mm in width parallel to a longitudinal continuous red line of not less than 150 mm in width; and
- (b) transverse yellow lines of not less than 200 mm in width and 1,200 mm in length,

as shown in diagrams 115(e) to 115(h) in Part III of the Schedule.

[S 639/2005 wef 03/10/2005]

(11AA) A bus-only lane is the section of a road, marked by —

- (a) a longitudinal continuous red line of not less than 300 mm in width; and
- (b) transverse red lines of not less than 200 mm in width and 1,200 mm in length.

[S 227/2026 wef 20/04/2026]

(11AB) The markings mentioned in paragraph (11AA) are shown in diagrams 115(i) to 115(l) in Part III of the Schedule.

[S 227/2026 wef 20/04/2026]

(11AC) A part-day bicycle lane is the section of a road, marked by —

- (a) a broken or continuous blue line; and
- (b) a bicycle symbol that appears at regular intervals on that section of the road.

[S 803/2022 wef 16/10/2022]

[S 227/2026 wef 20/04/2026]

(11AD) The markings mentioned in paragraph (11AC) are shown in diagrams 171, 172, 173(a) and (b) and 174 in Part III of the Schedule.

[S 803/2022 wef 16/10/2022]

[S 227/2026 wef 20/04/2026]

(11B) A full-day bicycle lane is the section of a road, marked by —

- (a) a longitudinal, continuous chevron marking; and
- (b) a bicycle symbol that appears at regular intervals on that section of the road.

[S 172/2017 wef 22/04/2017]

[S 803/2022 wef 16/10/2022]

(11C) The markings mentioned in paragraph (11B) are shown in diagrams 166, 167(a) and (b), 168(a), (b) and (c) and 169 in Part III of the Schedule.

[S 172/2017 wef 22/04/2017]

[S 803/2022 wef 16/10/2022]

(12) The boundary which no vehicle shall cross under paragraph (1)(m) is indicated by continuous double white lines as shown in diagram 150(a) in Part III of the Schedule.

(13) A parking place or a public service vehicle stand is indicated by broken or continuous lines as shown in diagram 156 in Part III of the Schedule.

(14) A Bus Give-Way Controlled Area is the section of a road marked by white triangle markings and the word “Bus” in white as shown in diagram 116(d) in Part III of the Schedule.

[S 651/2008 wef 20/12/2008]

(15) A Bus Give-Way Box is the section of a road painted in yellow and marked by an arrow, which —

(a) appears after a Bus Give-Way Controlled Area; and

(b) is separated from the Bus Give-Way Controlled Area by a Bus Give-Way Line,

as shown in diagram 116(d) in Part III of the Schedule.

[S 651/2008 wef 20/12/2008]

(16) An ERP Charge Zone may be indicated by all or any of the following:

(a) the traffic sign as shown in diagram 163(a), (b), (c) or (d) in Part III of the Schedule;

[S 291/2026 wef 15/05/2026]

(b) the marking as shown in diagram 163A(a) or (b) in Part III of the Schedule;

(c) an area of road that is painted in blue across the width of the road and which measures 25 metres in length along the direction of traffic flow, and such area may, in addition, be marked on each lane of the road by the letters “ERP” in

white as shown in diagram 163B in Part III of the Schedule;

[S 91/2026 wef 09/03/2026]

[S 291/2026 wef 15/05/2026]

(d) an area of road which measures 25 metres in length along the direction of traffic flow, where —

- (i) the edge of the road is indicated by a continuous blue line;
- (ii) each lane of the road is marked by the letters “ERP” in white as shown in diagram 163B in Part III of the Schedule; and
- (iii) the boundary between each lane of the road is indicated by broken blue lines.

[S 291/2026 wef 15/05/2026]

Bus lanes

8.—(1) Except on any Saturday, Sunday or public holiday, no person shall drive a vehicle other than an omnibus, or cause or permit any such vehicle to remain, on a part-day bus lane during the hours of 7.30 a.m. to 9.30 a.m. and 5 p.m. to 8 p.m.

[S 134/2007 wef 01/04/2007]

(1A) Except on any Sunday or public holiday, no person shall drive a vehicle other than an omnibus, or cause or permit any such vehicle to remain, on a full-day bus lane during the hours of 7.30 a.m. to 11 p.m.

[S 134/2007 wef 01/04/2007]

[S 114/2016 wef 21/03/2016]

(1B) A person must not drive a vehicle other than an omnibus, or cause or permit any such vehicle to remain, on a bus-only lane at all times.

[S 227/2026 wef 20/04/2026]

(2) Paragraphs (1), (1A) and (1B) shall not apply to —

- (a) the driver of an authorised ambulance, fire engine or any vehicle for police or rescue purposes on urgent duty call if

the approach of such vehicle is made known by means of some distinctive siren, bell or multi-toned horn, as the case may be;

[S 1056/2021 wef 03/01/2022]

- (b) a cyclist who is not cycling alongside of another bicycle, three-wheeled pedal cycle, recumbent device or power-assisted bicycle on his left;

[S 276/2018 wef 05/05/2018]

[S 170/2024 wef 01/03/2024]

- (c) the driver of a motor vehicle who drives along the bus lane in order to avoid causing danger to any person or a collision with any other vehicle if that driver does not cause or permit the vehicle to remain on the bus lane longer than is necessary to avoid causing such danger or collision;

[S 549/2001 wef 01/11/2001]

- (d) the driver of a school bus, a private hire bus or an excursion bus when it is used to carry passengers for reward under a Supplementary Public Transport Scheme in accordance with —

(i) a public service vehicle licence that is issued for that bus under section 102 of the Act; and

(ii) a bus service licence that is granted or is deemed granted under section 13 of the Bus Services Industry Act 2015 (Act 30 of 2015); and

[S 676/2016 wef 01/01/2017]

- (e) the driver of any other bus except that he shall not stop the bus in a bus lane or at a bus stand or bus bay within a bus lane for any purpose other than for the purpose of negotiating traffic.

[S 549/2001 wef 01/11/2001]

[S 114/2016 wef 21/03/2016]

[S 227/2026 wef 20/04/2026]

(2A) In addition, paragraph (1B) does not apply to —

- (a) the driver of a vehicle which is being used —
 - (i) by the Authority to carry out any function or duty of the Authority;
 - (ii) to carry out works on a public street, where such works have been approved by the Authority under section 17(1) of the Street Works Act 1995; or
 - (iii) to carry out any emergency works on a public street mentioned in regulation 31(1) of the Street Works (Works on Public Streets) Regulations (Rg 2);
- (b) the driver of a vehicle which has been authorised by the National Parks Board, the Public Utilities Board or the National Environment Agency (as the case may be) to be used to carry out any works that require the use of the bus-only lane and are necessary to carry out any function or duty of the National Parks Board, the Public Utilities Board or the National Environment Agency (as the case may be), other than the works mentioned in regulation 31(1) of the Street Works (Works on Public Streets) Regulations; and
- (c) the driver of a vehicle which has been authorised by the licensee of any bus interchange, bus park, bus terminal or bus depot (as the case may be) to be used by that licensee, provided that the vehicle is being driven on a bus-only lane that leads into or out of any bus interchange, bus park, bus terminal or bus depot, as the case may be.

[S 227/2026 wef 20/04/2026]

(3) In this rule —

“ambulance” means a motor vehicle that is specifically equipped for —

- (a) the transport on roads of; and
- (b) the provision, during such transport, of out-of-hospital clinical care to,

sick or injured individuals who require emergency medical treatment;

“authorised”, for an ambulance, means —

- (a) being specified in a licence (other than a revoked licence) under the Healthcare Services Act 2020 authorising the use of the ambulance to provide a licensable healthcare service specified in that licence; or
- (b) being owned by the Government and used for the purposes of the Singapore Armed Forces or the Singapore Civil Defence Force;

“bus lane” means any full-day or part-day bus lane, or bus-only lane.

[S 1056/2021 wef 03/01/2022]

[S 227/2026 wef 20/04/2026]

Bicycle lane

8A.—(1) A person must not park a vehicle —

- (a) on a part-day bicycle lane, on a Sunday at any time between 5 a.m. and 11 a.m.; or
- (b) on a full-day bicycle lane at any time.

(2) In this rule —

“full-day bicycle lane” has the meaning given by rule 7(11B);

“part-day bicycle lane” has the meaning given by rule 7(11AC).

[S 803/2022 wef 16/10/2022]

[S 227/2026 wef 20/04/2026]

Road divider

9. No vehicle shall pass over a road divider.

Light signals for vehicles

10. Vehicular traffic may be regulated by the following light signals:

- (a) a 3-colour system;
- (b) a 2-colour system;
- (c) lane use light signals; and
- (d) restricted zone light signals.

The 3-colour system

11. In a 3-colour system —

- (a) the signals shall consist of 3 lights, which shall be red, amber and green respectively, except that there may be —
 - (i) any red, amber or green arrow light;
 - (ii) any combination of red, amber or green arrow lights;
or
 - (iii) such other additional green light or lights as may be provided for in this rule for special purposes;
- (b) the signals shall consist of 3 arrows (either in left, right or straight ahead direction), which shall be red, amber and green respectively, except that there may be —
 - (i) any red, amber or green arrow light;
 - (ii) any combination of red, amber or green arrow lights;
or
 - (iii) such other additional green light or lights as may be provided for in this rule for special purposes;
- (c) the red, amber and green lights shall be arranged vertically or horizontally facing the direction of approaching traffic and —
 - (i) where they are arranged vertically, the red light shall be placed above the amber light and the green light shall be placed below the amber light;
 - (ii) where they are arranged horizontally, the red light shall be placed on the right of the amber light and the green light shall be placed on the left of the amber light;

- (iii) where they are arranged vertically with any combination of red, amber or green arrow lights, each arrow light shall be placed at the same level with a light of the same colour; and
- (iv) where they are arranged horizontally with any combination of red, amber or green arrow lights, each arrow light shall be placed below the light of the same colour;
- (d) any additional arrow light referred to in paragraph (a)(i) shall be placed —
 - (i) at the same level of the light of the same colour where the lights are arranged vertically;
 - (ii) above the red light where the lights are arranged vertically; or
 - (iii) below the light of the same colour where the lights are arranged horizontally;
- (e) any additional green light referred to in paragraph (a)(iii) shall be placed at the same level on the left side of or above the red light facing the direction of the approaching traffic where the lights are arranged vertically;
- (f) the red, amber and green arrow lights of the same direction shall be arranged vertically or horizontally facing the direction of approaching traffic and —
 - (i) where they are arranged vertically, the red arrow light shall be placed above the amber arrow light and the green arrow light shall be placed below the amber arrow light;
 - (ii) where they are arranged horizontally, the red arrow light shall be placed on the right of the amber arrow light and the green arrow light shall be placed on the left of the amber arrow light;
 - (iii) where they are arranged vertically with any combination of red, amber and green arrow lights

- of different directions, they shall be placed at the same level of the arrow lights of the same colour; and
- (iv) where they are arranged horizontally with any combination of red, amber and green arrow lights of different directions, they shall be placed below the arrow light of the same colour;
- (g) any additional arrow light referred to in paragraph (b) (i) shall be placed —
- (i) at the same level of the arrow light of the same colour where the arrow lights are arranged vertically;
 - (ii) above the red arrow light where the arrow lights are arranged vertically; and
 - (iii) below the arrow light of the same colour where the arrow lights are arranged horizontally;
- (h) any additional green light referred to in paragraph (b) (iii) shall be placed at the same level on the left side of or above the red arrow light facing the direction of the approaching traffic where the lights are arranged vertically;
- (i) where the lights and arrow lights are arranged vertically —
- (i) the effective diameter of the lens of each light and arrow light shall be at least 200 mm;
 - (ii) the height of the centre of the lens of the light or arrow light nearest to the ground surface shall be 2,290 mm except that it may be increased to 3,000 mm where owing to road gradient it is desirable to do so; and
 - (iii) the centres of the lenses of the 2 lights, 2 arrow lights or any combination thereof placed next to each other shall not be more than 500 mm apart;
- (j) where the lights and arrow lights are arranged horizontally —
- (i) the effective diameter of the lens of each light and arrow light shall be at least 300 mm;

- (ii) the height of the centre of the lens of the light or arrow light nearest to the ground surface shall not be less than 5,200 mm; and
- (iii) the centres of the lenses of the 2 lights, 2 arrow lights or any combination thereof placed next to each other shall not be more than 500 mm apart; and
- (k) subject to the directions of any police officer who may be engaged in the control of traffic —
 - (i) the illuminated red light shall be taken as prohibiting vehicles from proceeding beyond the stop line or broken lines on the road provided in conjunction with the signals, subject to sub-paragraphs (v), (ix), (x) and (xi);
 - (ii) the illuminated amber light shall be taken to denote an impending change from green light to red light and as prohibiting vehicles from proceeding beyond the stop line or broken lines on the road provided in conjunction with the signals except in the case of any vehicle which is so close to such line when the amber light first appears that it cannot safely be stopped before the line;
 - (iii) the illuminated green light shall be taken to indicate that vehicles may pass the signal and proceed straight on, or with due regard to the safety of other users of the road and precedence to pedestrians and on-coming traffic, turn left or right subject to any sign prohibiting left or right turn or in conjunction with the arrow light signals, subject to sub-paragraphs (x) and (xi);
 - (iv) where the green light shows one or more illuminated arrow or arrows, it shall be taken to indicate that vehicles may only proceed in the direction or directions indicated by the arrow or arrows (where the arrow points upwards, vehicles may only proceed straight ahead);

- (v) where the signals consist of one or more additional green arrow light or lights —
 - (A) the illuminated green arrow light or lights shall be taken to indicate that vehicles, notwithstanding that they would otherwise be required by the illuminated red or amber light to stop, may proceed in the direction or directions indicated by the green arrow or arrows with precedence to pedestrians; and
 - (B) the illuminated intermittent green arrow flashing light shall be taken as prohibiting vehicles from proceeding beyond the stop line on the road provided in conjunction with the signals except in the case of any vehicle which is so close to such line when the green arrow light first flashes that it cannot safely be stopped before the line;
 - (vi) where the signals consist of an additional green light showing the letter “B”, it shall be taken to indicate that any bus in the innermost left lane of the road before the stop line or broken lines on the road provided in conjunction with the signals may —
 - (A) notwithstanding that it would otherwise be required by the illuminated red light to stop; and
 - (B) if its path is not obstructed by another vehicle, pass the signal and proceed straight on;
- [S 549/2001 wef 01/11/2001]*
- (vii) the illuminated intermittent red light and the illuminated intermittent red arrow light flashing at the rate of between 60 to 80 flashes per minute shall be taken to indicate that vehicles shall stop at the stop line provided in conjunction with the signals and may thereafter, with caution and due regard to the safety of other users of the road and precedence to

pedestrians and to traffic in other directions, proceed beyond the stop line;

(viii) the illuminated intermittent amber light and the illuminated intermittent amber arrow light flashing at the rate of between 60 to 80 flashes per minute shall be taken to indicate that vehicles shall slow down on approaching the signals and may thereafter, with caution and due regard to the safety of other users of the road and precedence to pedestrians, proceed beyond the stop line provided in conjunction with the signals;

(ix) where allowed by the appropriate sign as shown in diagram 161 (a) or 161 (b) in Part III of the Schedule, a vehicle which —

(A) is on a lane from which a left turn or a right turn may, by virtue of any sign or marking as shown in the Schedule, be made; and

(B) in compliance with the illuminated red light, has stopped at the stop line or broken lines on the road provided in conjunction with the signals,

may, with caution and due regard to the safety of other users of the road and precedence to pedestrians and to traffic in other directions, proceed beyond the stop line or broken lines and make a left turn or a right turn, as the case may be;

(x) the illuminated red arrow light shall be taken as prohibiting vehicles from proceeding beyond the stop line or broken lines on the road in that direction, notwithstanding sub-paragraphs (vi) and (ix);

(xi) the illuminated amber arrow light shall be taken to denote an impending change from green arrow light to red arrow light and as prohibiting vehicles from proceeding beyond the stop line or broken lines on the road provided in conjunction with the signals

except in the case of any vehicle which is so close to such line when the amber arrow light first appears that it cannot safely be stopped before the line, notwithstanding that they would otherwise be required by the illuminated green or amber light or lights to proceed on; and

- (xii) the illuminated green arrow light shall be taken to indicate that vehicles, notwithstanding that they would otherwise be required by the illuminated red or amber lights to stop, may proceed in the direction or directions indicated by the green arrow or arrows with precedence to pedestrians.

[S 13/2000 wef 14/01/2000]

The 2-colour system

12.—(1) In a 2-colour system —

- (a) the signals shall consist of a red and green light; and
- (b) the red light and the green light shall not be illuminated simultaneously.

(2) The 2-colour system shall only be used in temporary installations.

Light signals for lanes

13. In the case of light signals regulating the use of traffic lanes —

- (a) the signals shall consist of 3 lights, which shall be a green downward arrow light, an amber inclined crossed bars light and a red inclined crossed bars light respectively and arranged horizontally facing the direction of approaching traffic;
- (b) the effective diameter of the lens of each light shall be at least 300 mm;
- (c) the height of the centre of the lens of each light above the road shall not be less than 5,200 mm;

- (d) the centres of the lenses of 2 lights placed next to each other shall not be more than 400 mm apart;
- (e) the illuminated green light shall be taken to indicate that vehicles may proceed along the lane over which the light is placed;
- (f) the illuminated intermittent amber flashing light shall be taken to indicate that vehicles may proceed with caution along the lane over which the light is placed; and
- (g) the illuminated red light shall be taken to indicate that vehicles shall not proceed beyond the signal light along the lane over which the light is placed.

Miniature light signals

14. The 3-colour system light signals may be supplemented with miniature light signals which shall be the same as the 3-colour system light signals where the red, amber and green lights are arranged vertically except that —

- (a) the effective diameter of the lens of each light shall be at least 100 mm;
- (b) the height of the centre of the lens of the green light above the road shall be at least 1,200 mm; and
- (c) the centres of the lenses of 2 lights placed next to each other shall not be more than 150 mm apart.

Light signals for cyclists, pedestrians and PMD riders

15.—(1) Light signals may be used to indicate to pedestrians, PMD riders and cyclists the period during which they should or should not cross the road.

[S 276/2018 wef 05/05/2018]

(2) The light signals for pedestrians, PMD riders and cyclists shall consist of one red light with the figure of a red man standing upright and one green light with the figure of a green man walking.

[S 276/2018 wef 05/05/2018]

(3) The effective diameter of the lens of each light shall not be less than 300 mm.

(4) The height of the centre of the lens of the green light above the road shall be 2,290 mm except that it may be increased where owing to road gradient it is desirable to do so.

(5) The centre of the lenses of the lights shall not be more than 350 mm apart.

(6) The post on which the lights are supported may be painted black and yellow in alternate horizontal bands.

(7) The illuminated red man light shall be taken to indicate that the pedestrian, PMD rider or cyclist shall not cross the road.

[S 276/2018 wef 05/05/2018]

(8) The illuminated green man light shall be taken to indicate that the pedestrian, PMD rider or cyclist may cross the road.

[S 276/2018 wef 05/05/2018]

(9) The flashing green man light shall be taken to indicate that the red man light is about to be illuminated.

[S 276/2018 wef 05/05/2018]

Light signals for bicycles, etc.

16.—(1) Light signals may be used to indicate to cyclists, PMD riders and pedestrians the period during which they should or should not cross the road, subway or bridge, as the case may be.

[S 276/2018 wef 05/05/2018]

(2) The light signals for cyclists, PMD riders and pedestrians shall consist of one red light with the picture of a red bicycle and one green light with the picture of a green bicycle.

[S 276/2018 wef 05/05/2018]

(3) The effective diameter of the lens of each light shall not be less than 300 mm.

(4) The height of the centre of the lens of the green light above the surface of the road, including that in a subway or on a bridge, as the case may be, shall be 2,290 mm except that it may be increased where owing to the gradient of the surface it is desirable to do so.

(5) The centre of the lens of the lights shall not be more than 350 mm apart.

(6) The post on which the lights are supported may be painted black and yellow in alternate horizontal bands.

(7) The illuminated red bicycle light shall be taken to indicate that the cyclist, PMD rider or pedestrian shall not cross the road.

[S 276/2018 wef 05/05/2018]

(8) The illuminated green bicycle light shall be taken to indicate that the cyclist, PMD rider or pedestrian may cross the road.

[S 276/2018 wef 05/05/2018]

(9) The flashing green bicycle light shall be taken to indicate that the red bicycle light is about to be illuminated.

[S 276/2018 wef 05/05/2018]

Temporary beacons

17.—(1) Temporary beacons showing an intermittent amber flashing light may be used on special occasions or in connection with road works to assist the safe movement of traffic.

(2) The temporary beacons shall conform to the following provisions:

- (a) the effective diameter of the lenses shall not be less than 125 mm nor more than 200 mm;
- (b) the height of the centre of the lens above the road shall not be less than 1,000 mm nor more than 1,200 mm;
- (c) the rate of flashing shall be between 60 to 80 flashes per minute; and
- (d) the beacons shall be mounted on a beam or a traffic cone or posted on to a barricade.

Temporary signs for road works

18.—(1) Where road works are in progress or where for some other reason the width of the road is temporarily reduced, the traffic signs in diagrams 7 and 8 in Part I of the Schedule may be used to control traffic.


(2) Nothing in this rule shall prevent the use for the purpose stated in paragraph (1) of devices which on 15th November 1991 are already in the possession of the Government, any statutory body which has the lawful authority to break up a road, or the contractors engaged in the business of marking and repairing roads.

THE SCHEDULE

PART I

MANDATORY SIGNS

DIAGRAM 1




AHEAD ONLY

This sign indicates that vehicles shall only proceed in the direction of the arrow. It may be further qualified when used with supplementary plates.

THE SCHEDULE — *continued*

DIAGRAM 2




TURN LEFT

The direction of the arrow may be reversed to indicate —

TURN RIGHT

This sign indicates that vehicles shall only proceed in the direction of the arrow. It may be further qualified when used with supplementary plates. It may also be used as a temporary sign to indicate diversion of traffic.

DIAGRAM 3



KEEP LEFT


THE SCHEDULE — *continued*

The direction of the arrow may be reversed to indicate —

KEEP RIGHT

This sign indicates that vehicles shall keep left (or right). It may be further qualified when used with supplementary plates.

DIAGRAM 4



TURN LEFT AHEAD


The direction of the arrow may be reversed to indicate —

TURN RIGHT AHEAD

This sign indicates that vehicles shall only turn in the direction of the arrow at the junction ahead. It may be further qualified when used with supplementary plates.

THE SCHEDULE — *continued*


DIAGRAM 5



PASS EITHER SIDE

This sign indicates that vehicles shall pass on either side of the sign.

DIAGRAM 6




THE SCHEDULE — *continued*

STOP CHILDREN

This sign indicates that vehicles shall not proceed beyond the sign.


DIAGRAM 7



This sign indicates that vehicles may proceed beyond the sign.


THE SCHEDULE — *continued*

DIAGRAM 8



This sign indicates that vehicles shall not proceed beyond the sign.

PRIORITY SIGNS


THE SCHEDULE — *continued*DIAGRAM 9

STOP

This sign indicates that vehicles shall, before entering the junction ahead, stop at the transverse stop line drawn in conjunction with the sign.

THE SCHEDULE — *continued*

DIAGRAM 10




GIVE WAY

This sign indicates that vehicles shall give precedence to the traffic on the left or right, as the case may be.


THE SCHEDULE — *continued*

DIAGRAM 10A




This sign indicates that vehicles shall stop before the Bus Give-Way Line and give precedence to any bus entering or waiting to enter the Bus Give-Way Box.

DIAGRAM 10B

THE SCHEDULE — *continued*

CARS AND MOTOR CYCLES ONLY LANE

This sign indicates that only cars and motor cycles may be used on such lanes found directly below this sign.

DIAGRAM 10C

ALL VEHICLES LANE


This sign indicates that any class of vehicles may be used on such lanes found directly below this sign. This sign serves as a supplement to diagram 10B and indicates that the lanes found directly below this sign are not subject to the prohibition or restriction in diagram 10B.

[S 189/2017 wef 28/04/2017]

[S 651/2008 wef 20/12/2008]

THE SCHEDULE — *continued*

PROHIBITORY AND RESTRICTIVE SIGNS


DIAGRAM 11

NO ENTRY

This sign prohibits the entry of all vehicles unless otherwise indicated by a supplementary plate.

THE SCHEDULE — *continued*


DIAGRAM 12



MAXIMUM SPEED LIMIT

This sign indicates that vehicles shall not travel at more than the speed of 50 km per hour. The numerals on the sign may be altered to indicate different speed limit.

DIAGRAM 12A

THE SCHEDULE — *continued*

SCHOOL ZONE, 40 KM/H

This sign is placed at the start of the demarcated school zone. It indicates that the section of road ahead is near a school and that vehicles must not travel at more than 40 km per hour in the school zone.

[S 690/2025 wef 01/01/2026]

DIAGRAM 12B(a)

THE SCHEDULE — *continued*


SILVER ZONE, 40 KM/H

This sign is placed at the start of a demarcated silver zone. It indicates that elderly pedestrians are likely to be encountered in the section of road ahead and that vehicles must not travel at more than 40 km per hour in the silver zone.

THE SCHEDULE — continued

[S 367/2024 wef 01/05/2024]

DIAGRAM 12B(b)




SILVER ZONE, 40 KM/H

This sign is placed at the start of a demarcated silver zone. It indicates that elderly pedestrians are likely to be encountered in the section of road ahead and that vehicles must not travel at more than 40 km per hour in the silver zone.

THE SCHEDULE — continued

[S 367/2024 wef 01/05/2024]
[S 95/2020 wef 01/03/2020]

DIAGRAM 12C(a)



THE SCHEDULE — *continued*

SILVER ZONE, 30 KM/H

This sign is placed at the start of a demarcated silver zone. It indicates that elderly pedestrians are likely to be encountered in the section of road ahead and that vehicles must not travel at more than 30 km per hour in the silver zone.

[S 367/2024 wef 01/05/2024]

DIAGRAM 12C(b)




SILVER ZONE, 30 KM/H

THE SCHEDULE — *continued*

This sign is placed at the start of a demarcated silver zone. It indicates that elderly pedestrians are likely to be encountered in the section of road ahead and that vehicles must not travel at more than 30 km per hour in the silver zone.


[S 367/2024 wef 01/05/2024]

DIAGRAM 12D(a)**“FRIENDLY STREETS”**

This sign is placed at the start of a zone demarcated as “Friendly Streets”. It indicates that vehicles must not travel at more than 40 km per hour in the demarcated zone.

[S 367/2024 wef 01/05/2024]

DIAGRAM 12D(b)

THE SCHEDULE — *continued*

“FRIENDLY STREETS”

This sign is placed at the start of a zone demarcated as “Friendly Streets”. It indicates that vehicles must not travel at more than 40 km per hour in the demarcated zone.


[S 367/2024 wef 01/05/2024]

[S 95/2020 wef 01/03/2020]

[S 670/2014 wef 01/10/2014]

THE SCHEDULE — *continued*

DIAGRAM 13




WIDTH LIMIT

This sign prohibits the entry of vehicles with width in excess of 2.3 metres. The numerals on the sign may be altered to indicate different width restriction.


THE SCHEDULE — *continued*

DIAGRAM 14




WEIGHT LIMIT

This sign prohibits the entry of vehicles with weight laden or unladen in excess of 10 tonnes. The numerals on the sign may be altered to indicate different weight restriction.

THE SCHEDULE — *continued*DIAGRAM 15

HEIGHT LIMIT

This sign prohibits the entry of vehicles with an overall height in excess of 4.5 metres. The numerals on the sign may be altered to indicate different height restriction.


THE SCHEDULE — *continued*DIAGRAM 16

NO WAITING

This sign prohibits the waiting of vehicles. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

THE SCHEDULE — *continued*

DIAGRAM 16 (b)




NO WAITING

This sign prohibits the waiting of vehicles, and indicates the point where the prohibition begins.

SCALE: 1:5

THE SCHEDULE — *continued*


DIAGRAM 16 (c)



NO WAITING


This sign prohibits the waiting of vehicles, and indicates the point where the prohibition ends.

SCALE: 1:5

THE SCHEDULE — *continued*DIAGRAM 17

NO STOPPING


This sign prohibits the stopping of vehicles unless the vehicle is prevented from proceeding due to traffic conditions. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

THE SCHEDULE — *continued*DIAGRAM 17 (a)

NO STOPPING

This sign prohibits the stopping of vehicles unless the vehicle is prevented from proceeding due to traffic conditions.

SCALE: 1:5

THE SCHEDULE — *continued*DIAGRAM 17 (b)


NO STOPPING

This sign prohibits the stopping of vehicles unless the vehicle is prevented from proceeding due to traffic conditions, and indicates the point where the prohibition begins.

SCALE: 1:5

THE SCHEDULE — *continued*


DIAGRAM 17 (c)



NO STOPPING


This sign prohibits the stopping of vehicles unless the vehicle is prevented from proceeding due to traffic conditions, and indicates the point where the prohibition ends.

SCALE: 1:5

THE SCHEDULE — *continued*DIAGRAM 18

NO OVERTAKING


This sign prohibits the overtaking of motor vehicles. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

THE SCHEDULE — *continued*DIAGRAM 19

LORRY RESTRICTION

This sign prohibits the entry of all goods vehicles. It may be further qualified when used with supplementary plates eg. "Exceeding 2,500 kg in unladen weight".


DIAGRAM 19A

THE SCHEDULE — *continued*

BUS AND GOODS VEHICLES RESTRICTION

This sign prohibits the entry of all buses and goods vehicles. It may be further qualified when used with supplementary plates.


[S 189/2017 wef 28/04/2017]

THE SCHEDULE — *continued*

RESTRICTION OF MOVEMENT OF VEHICLES WITH 3 OR MORE AXLES

THE SCHEDULE — *continued*

DIAGRAM 20A


RESTRICTION OF MOVEMENT OF TRAILERS
WITH CONTAINERS

This sign prohibits the movement of all trailers with containers on the section of the road beyond the point marked by the sign between 7.30 a.m. and 8 p.m. of any day from Monday to Friday (except public holidays). The days and times on the sign may be altered to indicate different days and times during which the prohibition applies.

[S 814/2013 wef 29/12/2013]

THE SCHEDULE — *continued*

DIAGRAM 21






PEDESTRIAN CROSSING PROHIBITION

This sign prohibits pedestrians, PMD riders and cyclists from crossing the road without using the designated pedestrian crossing. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.

[S 276/2018 wef 05/05/2018]


DIAGRAM 22



THE SCHEDULE — *continued*DIAGRAM 23DIAGRAM 24

THE SCHEDULE — *continued*

DIAGRAM 24 (a)



MESSAGE (BLACK)
ON REVERSED SIDE
(WHITE):—


1. CYCLISTS
Please Use Crossing
2. CYCLISTS
Please Use Underpass
3. CYCLISTS
Please Use Overpass



CYCLIST AND PMD RIDER CROSSING PROHIBITION

This sign indicates that cyclists and PMD riders shall not cross that section of the road, subway or bridge, as the case may be, without using the designated bicycle crossing. It may be used in conjunction with supplementary plates to indicate the section of that road, subway or bridge to which the prohibition applies.

[S 276/2018 wef 05/05/2018]

DIAGRAM 24 (b)




THE SCHEDULE — *continued*DIAGRAM 24 (c)DIAGRAM 24 (d)

CYCLIST AND PMD RIDER CROSSING PROHIBITION (MESSAGE ON
REVERSED SIDE)

DIAGRAM 24(e)


THE SCHEDULE — continued



PEDESTRIANS, CYCLISTS AND PMD RIDERS
CROSSING PROHIBITION SIGN

This sign prohibits pedestrians, cyclists and PMD riders from crossing the road without using the designated crossing. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.


DIAGRAM 24(f)



THE SCHEDULE — *continued*PEDESTRIANS, CYCLISTS AND PMD RIDERS
CROSSING PROHIBITION SIGN

This sign prohibits pedestrians, cyclists and PMD riders from crossing the road without using the designated crossing. This sign may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.


DIAGRAM 24(g)

PEDESTRIANS, CYCLISTS AND PMD RIDERS
USE CROSSING SIGN

This sign indicates that pedestrians, cyclists and PMD riders are to cross the road using the designated crossing.

DIAGRAM 24(h)


THE SCHEDULE — continued



PEDESTRIANS, CYCLISTS AND PMD RIDERS
USE OVERPASS SIGN

This sign indicates that pedestrians, cyclists and PMD riders are to cross the road using the designated overpass.


DIAGRAM 24(i)



THE SCHEDULE — *continued*PEDESTRIANS, CYCLISTS AND PMD RIDERS
USE UNDERPASS SIGN

This sign indicates that pedestrians, cyclists and PMD riders are to cross the road using the designated underpass.

[S 276/2018 wef 05/05/2018]




DIRECTIONAL ARROWS

These supplementary signs, when used in conjunction with prohibitory or restrictive signs, indicate the section of the road to which the prohibition or restriction applies.

THE SCHEDULE — *continued*


DIAGRAM 26

MOTOR CYCLES, POWER-ASSISTED BICYCLES AND PEDAL-CYCLES
RESTRICTION

This sign prohibits the entry of motor cycles, power-assisted bicycles and pedal-cycles ie. trishaws, three-wheeled pedal cycles, recumbent devices and bicycles.

[S 170/2024 wef 01/03/2024]


[S 276/2018 wef 05/05/2018]

THE SCHEDULE — *continued*DIAGRAM 27PEDESTRIAN, POWER-ASSISTED BICYCLES AND PEDAL-CYCLES
RESTRICTION

This sign prohibits the entry of pedestrians, power-assisted bicycles and pedal-cycles ie. trishaws, three-wheeled pedal cycles, recumbent devices and bicycles.

[S 170/2024 wef 01/03/2024]

[S 276/2018 wef 05/05/2018]

THE SCHEDULE — *continued*DIAGRAM 30

This sign prohibits the entry of bicycles and power-assisted bicycles.

[S 276/2018 wef 05/05/2018]

THE SCHEDULE — *continued*

DIAGRAM 30A



NO RIDING

This sign prohibits the riding of power-assisted bicycles and pedal-cycles, i.e. trishaws, three-wheeled pedal cycles, recumbent devices and bicycles, beyond the point marked by the sign. It may be used in conjunction with supplementary plates to indicate the section of the road to which the prohibition applies.


[S 170/2024 wef 01/03/2024]

[S 276/2018 wef 05/05/2018]

[S 577/2005 wef 05/09/2005]


THE SCHEDULE — *continued*

DIAGRAM 31



This sign prohibits the entry of motor cycles.

DIAGRAM 32




HAZARDOUS LOADS PROHIBITION

This sign prohibits the entry of vehicles transporting hazardous loads.

THE SCHEDULE — *continued*


DIAGRAM 33



NO RIGHT TURN

This sign prohibits vehicles from turning right at the junction ahead. It may be used in conjunction with traffic light signals and the prohibition may be qualified by a supplementary plate.

DIAGRAM 34




NO LEFT TURN

This sign prohibits vehicles from turning left at the junction ahead. It may be used in conjunction with traffic light signals and the prohibition may be qualified by a supplementary plate.

THE SCHEDULE — *continued*


DIAGRAM 35




NO HORNING

This sign prohibits horning except in an emergency.


DIAGRAM 36 (a)



This sign indicates a designated pay parking place for motor vehicles with weight unladen exceeding 1,500 kilograms.

THE SCHEDULE — *continued*


This sign indicates a designated pay parking place for motor vehicles with less than 4 wheels and the weight of which unladen does not exceed 470 kilograms.



This sign indicates a designated pay parking place for motor vehicles, the weight of which unladen does not exceed 1,500 kilograms.


THE SCHEDULE — *continued*

DIAGRAM 36 (d)



PARKING PLACES SIGN (URA)

This sign indicates a designated pay parking place where parking coupons are to be used.


THE SCHEDULE — *continued*

PARKING PLACE SIGN (HDB)

This sign indicates a designated pay parking place where parking coupons are to be used and/or where season parking is applicable.

THE SCHEDULE — *continued*


DIAGRAM 36 (f)



NO PARKING OF BUS AND LORRY

This sign prohibits the parking of buses and lorries.


DIAGRAM 37



THE SCHEDULE — *continued*

This marking indicates that vehicles on the lane with the marking may only proceed ahead.


DIAGRAM 38



This marking indicates that vehicles on the lane with the marking may only turn left or right.

THE SCHEDULE — *continued*


DIAGRAM 39



This marking indicates that vehicles on the lane with the marking may only proceed straight ahead or turn right.

THE SCHEDULE — *continued*


DIAGRAM 40



This marking indicates that vehicles on the lane with the marking may only turn right.

THE SCHEDULE — *continued*

DIAGRAM 40A



NO WALKING WITHIN BUS PARK

This sign indicates that unauthorised persons are prohibited from walking within the bus park.

[S 334/2003 wef 14/07/2003]


[S 367/2024 wef 01/05/2024]

PART II

WARNING SIGNS

THE SCHEDULE — *continued*


DIAGRAM 41



TWO WAY TRAFFIC

This sign indicates that the section of the road ahead carries two-way traffic.

DIAGRAM 42




TWO-WAY TRAFFIC ACROSS A ONE-WAY CARRIAGEWAY

This sign indicates that the transverse road ahead carries two-way traffic.

THE SCHEDULE — *continued*


DIAGRAM 43



ROAD NARROWS ON BOTH SIDES AHEAD

This sign indicates that the road ahead narrows on both sides.

DIAGRAM 44



ROAD NARROWS ON RIGHT AHEAD


This symbol may be reversed to indicate —

ROAD NARROWS ON LEFT AHEAD

This sign indicates that the road ahead narrows on the right (or left) side.

THE SCHEDULE — *continued*

DIAGRAM 45




BEND TO THE RIGHT AHEAD

This symbol may be reversed to point to the left to indicate —

BEND TO THE LEFT AHEAD

This sign indicates that the road ahead bends to the right (or left).

DIAGRAM 46



DOUBLE BEND AHEAD, FIRST TO THE LEFT


This symbol may be reversed to indicate —

DOUBLE BEND AHEAD, FIRST TO THE RIGHT

This sign indicates that there is a double bend of the road ahead.

THE SCHEDULE — *continued*

DIAGRAM 47




SERIES OF BENDS FIRST TO THE RIGHT

This symbol may be reversed to indicate —

SERIES OF BENDS FIRST TO THE LEFT

This sign indicates that there is a series of bends of the road ahead.

DIAGRAM 48



SIDE ROAD TO THE RIGHT


This symbol may be reversed to indicate —

SIDE ROAD TO THE LEFT

THE SCHEDULE — *continued*

This sign indicates that there is a side road junction ahead.

DIAGRAM 49




STAGGERED JUNCTION, LEFT TURN FIRST

This symbol may be reversed to indicate —

STAGGERED JUNCTION, RIGHT TURN FIRST

This sign indicates that there is a staggered junction ahead.

DIAGRAM 50




CROSS ROADS

This sign indicates that there is a cross roads junction ahead.

THE SCHEDULE — *continued*

DIAGRAM 51




MERGING INTO TRAFFIC ON RIGHT

This symbol may be reversed to indicate —

MERGING INTO TRAFFIC ON LEFT

This sign indicates that there a junction ahead where traffic on this road will merge with the traffic on the adjoining road.

DIAGRAM 52



TRAFFIC MERGES FROM LEFT


This symbol may be reversed to indicate —

TRAFFIC MERGES FROM RIGHT

This sign indicates that traffic on the adjoining road will merge into traffic on this road.

THE SCHEDULE — *continued*


DIAGRAM 53



T-JUNCTION

This sign indicates that there is a T-junction ahead.

DIAGRAM 54




DUAL CARRIAGEWAY ENDS AHEAD

This sign indicates that the dual carriageways will merge into a single carriageway ahead.

THE SCHEDULE — *continued*


DIAGRAM 55



ROUNDBOUT AHEAD

This sign indicates that there is a roundabout ahead.

DIAGRAM 56




TRAFFIC SIGNALS AHEAD

This sign indicates that traffic is controlled by traffic light signals ahead.

THE SCHEDULE — *continued*

DIAGRAM 57




PEDESTRIAN CROSSING AHEAD

This sign indicates that there is a pedestrian crossing ahead.

THE SCHEDULE — *continued*

DIAGRAM 57 (a)




BICYCLE CROSSING AHEAD

This sign indicates that there is a bicycle crossing ahead.

THE SCHEDULE — continued

DIAGRAM 57(b)




PEDESTRIAN CROSSING AHEAD MARKING

This marking indicates that there is a zebra crossing ahead and motorists should be prepared to give way to pedestrians crossing the road at the zebra crossing.

[S 257/2009 wef 08/06/2009]

DIAGRAM 57(c)




ADVANCED WARNING LIGHTS

THE SCHEDULE — *continued*

The flashing amber lights indicate to motorists that the traffic light signal ahead is red or going to turn red and motorists should slow down and prepare to stop.

[S 257/2009 wef 08/06/2009]

DIAGRAM 57(d)




INTELLIGENT ROAD STUDS

These intelligent road studs, mounted flush to the road surface, blink when the green man light of the associated pedestrian crossing is illuminated. They indicate to motorists turning right that they should give way to pedestrians crossing the road.

[S 257/2009 wef 08/06/2009]

DIAGRAM 57(e)


THE SCHEDULE — *continued*

GIVE WAY TO PEDESTRIANS

This sign is placed at a signalised junction, and is usually mounted on top of a traffic light. It indicates for right turning motorists to look out for and to give way to adjacent crossing pedestrians.

[S 158/2018 wef 01/04/2018]


THE SCHEDULE — *continued*



CHILDREN

This sign indicates that there is ahead an area where children are likely to be encountered.

DIAGRAM 58(a)




SCHOOL ZONE DRIVE CAREFULLY

THE SCHEDULE — *continued*

This sign is placed at the start of a demarcated school zone.
It indicates that the section of the road ahead is near a school.

[S 690/2025 wef 01/01/2026]

[S 782/2013 wef 01/01/2014]

DIAGRAM 58(b)

SCHOOL ZONE DRIVE CAREFULLY


This sign is placed at the start of a demarcated school zone.
It indicates that the section of the road ahead is near a school.

[S 690/2025 wef 01/01/2026]

[S 782/2013 wef 01/01/2014]

THE SCHEDULE — *continued*


DIAGRAM 59



PEDESTRIAN ON ROAD AHEAD

This sign indicates that there is ahead an area where pedestrian are likely to be encountered.

DIAGRAM 59A




“LOOK” MARKING

This marking is indicated on the road pavement to remind pedestrians to look out for traffic before crossing the road.

[S 158/2018 wef 01/04/2018]

DIAGRAM 59B


THE SCHEDULE — *continued*



WATCH OUT FOR VEHICLES


This sign informs pedestrians to watch out for oncoming vehicles before crossing the road.

[S 158/2018 wef 01/04/2018]




STEEP HILL UPWARDS AHEAD

This sign indicates that there is a steep hill upwards ahead.

THE SCHEDULE — *continued*DIAGRAM 61

STEEP HILL DOWNWARDS AHEAD

This sign indicates that there is a steep hill downwards ahead.


DIAGRAM 62

SLIPPERY ROAD AHEAD

This sign indicates that the condition of the road surface ahead is dangerous.

THE SCHEDULE — *continued*


DIAGRAM 63



UNEVEN ROAD


This sign indicates that the road ahead is uneven.

DIAGRAM 64




HEIGHT LIMIT AHEAD

This sign indicates that the section of the road ahead has a height restriction of 4.5m. The numerals on the sign may be altered to indicate different height restriction.

THE SCHEDULE — *continued*

LEVEL CROSSING WITH GATE OR BARRIER AHEAD

This sign indicates that there is a level crossing with gate or barrier ahead.




LEVEL CROSSING WITHOUT GATE OR BARRIER AHEAD

This sign indicates that there is a level crossing without gate or barrier ahead.

THE SCHEDULE — continued


DIAGRAM 67



HORSES OR PONIES

This sign indicates that there is ahead an area where horses are likely to be encountered.

DIAGRAM 68




ROAD HUMP AHEAD

This sign indicates that there is a road hump ahead.

THE SCHEDULE — *continued*


DIAGRAM 69



NARROW BRIDGE AHEAD


This sign indicates that there is a narrow bridge ahead.

DIAGRAM 70



QUAYSIDE OR RIVER BANK AHEAD

This sign indicates that there is a quayside or river bank ahead.


THE SCHEDULE — *continued*DIAGRAM 71

OTHER DANGER

This sign indicates that there is ahead potential danger which is not covered specifically by any other warning sign.

THE SCHEDULE — *continued*

DIAGRAM 72 (a)




LANE CLOSURE AHEAD

OFFSIDE LANE CLOSED

This symbol may be reversed to indicate —


NEARSIDE LANE CLOSED

This sign indicates that there is ahead closure of the lane marked by the red bar.

THE SCHEDULE — *continued*

CENTRE LANE CLOSURE AHEAD

This sign indicates that there is ahead closure of the centre lane marked by the red bar.



ACCIDENT AREA

This sign indicates the section of the road which is prone to accidents.

THE SCHEDULE — continued

This sign indicates that there is ahead an area where elderly or handicapped pedestrians are likely to be encountered.



SILVER ZONE, SLOW DOWN

This sign is placed at the start of a demarcated silver zone. It indicates that elderly pedestrians are likely to be encountered in the section of road ahead and that motorists should slow down.

DIAGRAM 76B




THE SCHEDULE — *continued*

This sign indicates that motorists must keep a lookout for cyclists.

[S 172/2017 wef 22/04/2017]

[S 670/2014 wef 01/10/2014]

DIAGRAM 77



DIVERSION TO ANOTHER CARRIAGEWAY TO THE RIGHT


This symbol may be reversed to indicate —

DIVERSION TO ANOTHER CARRIAGEWAY TO THE LEFT

This sign indicates that there is a diversion of carriageway ahead.

THE SCHEDULE — *continued*


DIAGRAM 78



DANGER


This sign indicates an obstruction ahead.

DIAGRAM 79




MERGE

This sign indicates that there is a merging of traffic ahead.

THE SCHEDULE — *continued*


U-TURN AHEAD

This sign indicates that vehicles may be making a U-Turn ahead.




U-TURN AHEAD (FROM OPPOSITE DIRECTION)

This sign indicates that vehicles from the opposite direction may be making a U-Turn ahead.

THE SCHEDULE — *continued*DIAGRAM 83

TUNNEL AHEAD

This sign indicates that the stretch of road ahead runs through a tunnel.

DIAGRAM 83A


TUNNEL

This sign serves as a supplement to diagram 83 and indicates the presence of a tunnel ahead.

[S 189/2017 wef 28/04/2017]

THE SCHEDULE — *continued*


DIAGRAM 84



SHARP DEVIATION

This sign indicates that there is a sharp deviation in the road to the left.


DIAGRAM 84A



CURVE ALIGNMENT MARKER

This marking is installed along sharp road bends to indicate to motorists that they are approaching the bends.

[S 158/2018 wef 01/04/2018]



THE SCHEDULE — *continued*DIAGRAM 85

BARRIER


This sign indicates a temporary barrier.

PART III

INFORMATIVE SIGNS

DIAGRAM 86 (a)DIAGRAM 86 (b)


ADVANCE DIRECTIONAL SIGNS

DIAGRAM 86 (c)DIAGRAM 86 (d)


CONFIRMATORY SIGNS

THE SCHEDULE — *continued*


Note: In diagrams 86(a) to 86(d), the background of the signs may be in green, blue or white. The symbols and inscriptions on a coloured background are in white or yellow and on a white background, in black.

DIAGRAM 86 (e)

ROCHOR ROAD, KEEP LEFT


DIAGRAM 86 (f)

PUBLIC CAR PARK

THE SCHEDULE — *continued*DIAGRAM 87

NO THROUGH ROAD

This sign placed at the entry to a road indicates a no through road.


DIAGRAM 88

NO THROUGH ROAD ON SIDE ROAD TO THE RIGHT

This symbol may be reversed to indicate —

NO THROUGH ROAD ON SIDE ROAD TO THE LEFT

This sign indicates that the road on the right (or left) is a no through road.

THE SCHEDULE — *continued*


ONE WAY STREET

ONE WAY STREET TO LEFT

The arrow may be reversed to point right to indicate —


ONE WAY STREET TO RIGHT

The above indicates that the traffic flow along the road ahead is a one way to the left (or right).




ONE WAY TRAFFIC

This sign indicates the direction of traffic flow on a one way street.

THE SCHEDULE — *continued*DIAGRAM 91

U-TURN


This sign indicates that there is ahead a facility where vehicles are permitted to make a U-Turn.

DIAGRAM 92

U-TURNING VEHICLES KEEP RIGHT


THE SCHEDULE — *continued*

DIAGRAM 93



DUAL CARRIAGEWAY AHEAD


DIAGRAM 94



SLOW


THE SCHEDULE — *continued*

DIAGRAM 95



REDUCE SPEED NOW

DIAGRAM 95A




‘YOUR SPEED’ SIGN

The electronic sign will flash a motorist's real time speed, thereby indicating to the motorist whether he should slow down to obey the speed limit.

[S 257/2009 wef 08/06/2009]

THE SCHEDULE — *continued*

DIAGRAM 96




RED LIGHT CAMERA


DIAGRAM 97



KEEP LEFT UNLESS OVERTAKING

THE SCHEDULE — *continued*DIAGRAM 98


END OF RESTRICTED ZONE

DIAGRAM 99

START OF EXPRESSWAY

THE SCHEDULE — *continued*


DIAGRAM 100



END OF EXPRESSWAY

TYPE I


DIAGRAM 101



END OF EXPRESSWAY


THE SCHEDULE — *continued*

DIAGRAM 102



END OF EXPRESSWAY AHEAD

DIAGRAM 103




START OF EXPRESSWAY

This sign indicates the start of an expressway.



THE SCHEDULE — *continued*

DIAGRAM 104



END OF EXPRESSWAY

This sign indicates the end of an expressway.

THE SCHEDULE — *continued*DIAGRAM 105DIAGRAM 106

EXPRESSWAY KILOMETRE SIGN


Diagram 107(a)

[Deleted by S 538/2011 wef 21/09/2011]

THE SCHEDULE — *continued*

Diagram 107(b)

[Deleted by S 538/2011 wef 21/09/2011]




TAXI STOP

This sign indicates the location of a taxi stop.

[S 165/2011 wef 29/03/2011]

THE SCHEDULE — *continued*

DIAGRAM 107(d)



TAXI STOP

This sign indicates the specified number of taxis that may use the taxi stop at any one time.

[S 165/2011 wef 29/03/2011]

DIAGRAM 107(e)



P2P STOP

This sign indicates the location of a P2P stop.

[S 883/2025 wef 01/01/2026]


THE SCHEDULE — *continued*

Diagram 108

[Deleted by S 538/2011 wef 21/09/2011]

Diagram 108A

[Deleted by S 538/2011 wef 21/09/2011]



TAXI STAND


This sign indicates the location of a taxi stand.

[S 165/2011 wef 29/03/2011]

THE SCHEDULE — continued

Diagram 110

[Deleted by S 538/2011 wef 21/09/2011]



TAXI DROP-OFF POINT

This sign indicates the location of a taxi drop-off point.


[S 375/2001 wef 03/08/2001]

Diagram 111

[Deleted by S 538/2011 wef 21/09/2011]

THE SCHEDULE — *continued*

DIAGRAM 111A




TAXI ADVISORY

This sign informs passengers that it is illegal for taxi drivers to tout or overcharge.

[S 165/2011 wef 29/03/2011]


DIAGRAM 112



QUEUE HERE FOR TAXI

THE SCHEDULE — *continued*

DIAGRAM 113



MARKING AT THE START OF A PART-DAY AND FULL-DAY BUS LANE

[S 639/2005 wef 03/10/2005]

THE SCHEDULE — *continued*

DIAGRAM 114



PART-DAY BUS LANE

[S 134/2007 wef 01/04/2007]

THE SCHEDULE — *continued*

DIAGRAM 114A



FULL-DAY BUS LANE

DIAGRAM 114B

THE SCHEDULE — *continued*


BUS-ONLY LANE

[S 227/2026 wef 20/04/2026]

[S 114/2016 wef 21/03/2016]

[S 134/2007 wef 01/04/2007]

DIAGRAM 115 (a)



THE SCHEDULE — *continued*

AT SIGNALISED INTERSECTION FOR PART-DAY BUS LANE

[S 639/2005 wef 03/10/2005]

DIAGRAM 115 (b)




DIAGRAM 115 (c)





DIAGRAM 115 (d)




AT UNCONTROLLED JUNCTIONS
OR OPENINGS

PART-DAY BUS LANE MARKINGS

[S 639/2005 wef 03/10/2005]

DIAGRAM 115 (e)




THE SCHEDULE — *continued*

AT SIGNALISED INTERSECTION FOR FULL-DAY BUS LANE


[S 639/2005 wef 03/10/2005]

DIAGRAM 115 (f)




[S 639/2005 wef 03/10/2005]

DIAGRAM 115 (g)



[S 639/2005 wef 03/10/2005]

DIAGRAM 115 (h)




THE SCHEDULE — *continued*

AT UNCONTROLLED JUNCTIONS OR OPENINGS


FULL-DAY BUS LANE MARKINGS

DIAGRAM 115(i)



AT SIGNALISED INTERSECTION FOR BUS-ONLY LANE

DIAGRAM 115(j)




BUS-ONLY LANE AT UNCONTROLLED JUNCTION OR OPENING

DIAGRAM 115(k)

THE SCHEDULE — *continued*


DIAGRAM



BUS-ONLY LANE AT UNCONTROLLED JUNCTION OR OPENING

DIAGRAM 115(l)

DIAGRAM




BUS-ONLY LANE AT UNCONTROLLED JUNCTION OR OPENING

[S 227/2026 wef 20/04/2026]

[S 639/2005 wef 03/10/2005]

THE SCHEDULE — continued


DIAGRAM 116 (a)



BUS STOP

This sign indicates the location of bus stop.

DIAGRAM 116(aa)




BUS STOP

This sign indicates the location of a bus stop.

[S 375/2001 wef 03/08/2001]


THE SCHEDULE — *continued*

DIAGRAM 116 (b)



This sign indicates the location of bus terminus.


DIAGRAM 116 (c)



BUS ZONE

The markings indicate a bus zone box reserved for an omnibus to pick up or set down passengers.

DIAGRAM 116(d)




THE SCHEDULE — *continued*

MARKINGS FOR A BUS GIVE-WAY
CONTROLLED AREA, BUS GIVE-WAY LINE
AND BUS GIVE-WAY BOX

[S 651/2008 wef 20/12/2008]


DIAGRAM 117



RAIN SHELTER

This sign indicates the location of rain shelter.


DIAGRAM 118



THE SCHEDULE — *continued*


CONCEALED EXIT AHEAD

DIAGRAM 119




EXCEPT SCHOOL BUSES

DIAGRAM 120



EXCEEDING 2,500 KG IN UNLADEN WEIGHT

DIAGRAM 121






THE SCHEDULE — *continued*


DIAGRAM 124



VEHICLES NOT EXCEEDING 2,500 KG IN UNLADEN WEIGHT

THE SCHEDULE — *continued*


DIAGRAM 125 (a)



PEDESTRIAN CROSSING

This sign indicates the location of a pedestrian crossing.

DIAGRAM 126




DIRECTION OF TEMPORARY PEDESTRIAN ROUTE

This sign indicates that there is a temporary footway for pedestrian to the left. The arrow may be reversed or a double headed arrow may be used to indicate a temporary footway for pedestrian to the right or to the left and right respectively.

THE SCHEDULE — *continued*


DIAGRAM 127



UNDERPASS

This sign indicates the location of a pedestrian underpass.

DIAGRAM 128




OVERPASS

This sign indicates the location of a pedestrian overpass.

THE SCHEDULE — *continued*

DIAGRAM 129 (a)




RED MAN

GREEN MAN

LIGHT SIGNALS FOR PEDESTRIANS


DIAGRAM 129 (b)



GREEN LIGHT SIGNAL FOR OMNIBUSES

THE SCHEDULE — continued


DIAGRAM 129 (c)



BICYCLE CROSSING

This sign indicates the location of a bicycle crossing.

DIAGRAM 129(ca)




BICYCLE CROSSING SIGN

THE SCHEDULE — *continued*

This sign indicates the location of a bicycle crossing.

[S 276/2018 wef 05/05/2018]

DIAGRAM 129 (d)




DIRECTION OF TEMPORARY CYCLIST ROUTE


This sign indicates that there is a temporary pathway for cyclist to the left. The arrow may be reversed or a double headed arrow may be used to indicate a temporary footway for cyclist to the right or to the left and right respectively.

THE SCHEDULE — *continued*

DIAGRAM 129 (e)



RED BICYCLE




GREEN BICYCLE

LIGHT SIGNALS FOR BICYCLES

THE SCHEDULE — *continued*


DIAGRAM 130




SCALE: 1:20

THE SCHEDULE — *continued*

DIAGRAM 131




SCALE: 1:20

THE SCHEDULE — *continued*DIAGRAM 132

SPEED REGULATING STRIPS AHEAD


THE SCHEDULE — *continued*

DIAGRAM 133




THE SCHEDULE — *continued*

DIAGRAM 134



THE SCHEDULE — *continued*

DIAGRAM 135A




TRAFFIC CALMING MARKINGS

These markings consist of 2 rows of white triangles which are intended to create a visually narrowed lane to slow down the speed of motorists.

[S 257/2009 wef 08/06/2009]

THE SCHEDULE — *continued*


DIAGRAM 136



START OF TUNNEL

THE SCHEDULE — *continued*


DIAGRAM 137



LANE INDICATION ARROWS (WITH TIME RESTRICTIONS)


THE SCHEDULE — *continued*

DIAGRAM 138 (a)



MERGE ARROWS


This marking indicates that the 2 lanes with the marking will merge into a single lane ahead.

THE SCHEDULE — *continued*DIAGRAM 138 (b)

SHARED ARROW

THE SCHEDULE — *continued*


This marking indicates that vehicles on the lane with the marking may only proceed ahead, turn left or right.



EDGE OF ROAD MARKINGS

THE SCHEDULE — *continued*

DIAGRAM 140 (a)




MARKINGS AT SIGNAL-CONTROLLED JUNCTION

[S 572/2005 wef 01/09/2005]


THE SCHEDULE — *continued*

DIAGRAM 140 (b)



YELLOW BOX AT JUNCTION


DIAGRAM 140 (c)



YELLOW BOX NEAR BUS BAY

THE SCHEDULE — *continued*


DIAGRAM 140 (d)



YELLOW BOX AT EXIT OF SLIP ROAD

THE SCHEDULE — *continued*

DIAGRAM 140 (e)




MARKINGS AT SIGNAL-CONTROLLED JUNCTION

[S 572/2005 wef 01/09/2005]


THE SCHEDULE — *continued*

DIAGRAM 140 (f)




YELLOW BOX NEAR 'U' TURN OPENING

DIAGRAM 140 (g)



YELLOW BOX NEAR DEMARCATED BUS BAY


DIAGRAM 140 (h)



YELLOW BOX NEAR DRIVEWAY


THE SCHEDULE — *continued*

DIAGRAM 140 (i)



YELLOW BOX NEAR BAY

DIAGRAM 141




RIGHT TURN POCKET

This marking is intended to guide motorists making a right turning at a junction as to the path they should take.


THE SCHEDULE — *continued*

DIAGRAM 142 (a)




THE SCHEDULE — *continued*

DIAGRAM 142 (b)




THE SCHEDULE — *continued*

DIAGRAM 143 (a)




THE SCHEDULE — *continued*

DIAGRAM 143 (b)




THE SCHEDULE — *continued*

DIAGRAM 144 (a)




THE SCHEDULE — *continued*

DIAGRAM 144 (b)



THE SCHEDULE — *continued*


DIAGRAM 145



SIGNALISED PEDESTRIAN CROSSING

[S 572/2005 wef 01/09/2005]

DIAGRAM 145(a)




SIGNALISED BICYCLE CROSSING

[S 276/2018 wef 05/05/2018]

THE SCHEDULE — *continued*


DIAGRAM 146

U-TURN MARKINGS



TYPICAL U-TURN MARKINGS ON A DUAL-CARRIAGEWAY


SCALE: 1:1000



U-TURN MARKINGS

THE SCHEDULE — *continued*


DIAGRAM 147



DOUBLE LINES AND HATCHED MARKINGS ON SHARP BENDS

THE SCHEDULE — *continued*

DIAGRAM 147A




BROADER ALIGNMENT LANE MARKINGS (BALM)

These markings are found along bends on expressways and major arterial roads. The markings guide motorists to be better aligned to their lanes.

[S 158/2018 wef 01/04/2018]


DIAGRAM 148 (a)



DIVERGING TRAFFIC


THE SCHEDULE — *continued*

DIAGRAM 148 (b)




MERGING TRAFFIC

DIAGRAM 148 (c)



TWO WAY TRAFFIC CHEVRON MARKINGS

DIAGRAM 149 (a)




ACCELERATION LANE

SINGLE ENTRY

THE SCHEDULE — *continued*


DIAGRAM 149 (b)



DECELERATION LANE

SINGLE ENTRY

DIAGRAM 149 (c)



CHEVRON MARKINGS FOR EXPRESSWAY

THE SCHEDULE — continued

DIAGRAM 149 (d)






DIAGRAM 149 (e)




THE SCHEDULE — *continued*DIAGRAM 149 (f)**INCLINED BROKEN YELLOW LINE**


The line is used to guide drivers emerging from the side road to keep away from the leftmost traffic lane which is a bus lane. It gives the road user advance warning and provides clearer guidance to motorists of bus lane ahead.

DIAGRAM 150 (a)**LONGITUDINAL MARKINGS****CENTRE / LANE LINES****A**


DOUBLE WHITE LINES AT THE CENTRE OF A TWO WAY ROAD
OR BETWEEN LANES

THE SCHEDULE — *continued*DIAGRAM 150 (b)


SINGLE WHITE LINE AT THE CENTRE OF A TWO WAY ROAD

DIAGRAM 150 (c)


BROKEN WHITE LINES AT THE CENTRE OF A TWO WAY ROAD

DIAGRAM 150 (d)

BROKEN WHITE LINES BETWEEN LANES


THE SCHEDULE — *continued*DIAGRAM 151 (a)

BROKEN WHITE LINES BETWEEN LANES
INDICATING THE APPROACH TO A STOP LINE AT A JUNCTION


DIAGRAM 151 (b)

BROKEN WHITE LINES INDICATING THE EDGE OF
THE MAIN ROAD AT —


- (i) Bus Bay and Lay-Bys
- (ii) Slip road, including acceleration and deceleration lanes
- (iii) Exclusive right turn lanes

DIAGRAM 151 (c)


BROKEN WHITE LINES INDICATING THE EDGE OF
UNDIVIDED STRAIGHT ROAD

THE SCHEDULE — *continued*DIAGRAM 151 (d)


SINGLE WHITE LINE INDICATING THE EDGE OF A ROAD WHERE
THERE IS IMMINENT HAZARD

DIAGRAM 151 (e)

SINGLE WHITE LINE DEMARCATING THE HARD SHOULDER
SECTION ON AN EXPRESSWAY

DIAGRAM 151 (f)


An edgeline is a continuous white line of a width of 200 mm painted alongside the edge of a carriageway or alongside the central dividing kerb of a dual carriageway. It is a supplementary guiding line to be provided on selected roads wherever necessary.

DIAGRAM 152 (a)PARKING RESTRICTION LINES

Single yellow line at the edge of a road prohibiting parking from 7am to 7pm on any day except Sundays or gazetted public holidays.


THE SCHEDULE — *continued*

DIAGRAM 152 (b)



Double yellow lines at the edge of a road prohibiting parking at all times.


DIAGRAM 152 (c)



Single zig zag yellow line at the edge of a road prohibiting parking at all times.


THE SCHEDULE — continued

DIAGRAM 152 (d)



Double zig zag yellow lines at the edge of a road prohibiting stopping of vehicles at all times unless the vehicle is prevented from proceeding due to traffic conditions.


DIAGRAM 152(e)




The red transverse lines of not less than 1,000 mm in width are laid down perpendicular to the edge of a road. These lines indicate that the parking of any vehicle is prohibited along the length of the road starting from the point where those lines are indicated, to the point the lines end.

[S 172/2017 wef 22/04/2017]


TRANSVERSE MARKINGS

THE SCHEDULE — *continued***A STOP LINE**DIAGRAM 153

Single white line indicating position on a road where vehicles are required to stop in compliance with a 'STOP' sign, traffic signal or the direction of police officers.

B GIVE WAY LINEDIAGRAM 154


Broken double white lines indicating the position on a road where vehicles are required to give way to traffic on the right or left, as the case may be, in compliance with a 'GIVE WAY' sign.

C GIVE WAY TRIANGULAR MARKINGDIAGRAM 155

Marking indicating that vehicles are required to give way to traffic on the right or left, as the case may be.

THE SCHEDULE — *continued*


DIAGRAM 156



TYPICAL ARRANGEMENT OF PARKING LOTS

THE SCHEDULE — *continued*

DIAGRAM 157




This sign indicates that the parking lot is reserved for a vehicle driven by a disabled person.

[Diagrams 158 and 159 deleted by S 461/98]


THE SCHEDULE — *continued*

DIAGRAM 160 (a)




THE SCHEDULE — continued

DIAGRAM 160 (b)




THE SCHEDULE — *continued*


DIAGRAM 160 (d)



THE SCHEDULE — *continued*


DIAGRAM 160 (f)



THE SCHEDULE — *continued*DIAGRAM 161 (a)


THE SCHEDULE — *continued*

DIAGRAM 161 (b)



THE SCHEDULE — *continued*

DIAGRAM 161 (c)



THE SCHEDULE — *continued*

DIAGRAM 161 (d)






DIAGRAM 161 (e)



THE SCHEDULE — *continued*

DIAGRAM 161 (g)



[S 3/2005 wef 03/01/2005]

THE SCHEDULE — *continued*

DIAGRAM 162





DIAGRAM 163(a)

**SIZE:**

600mm X 600mm


This sign is placed facing approaching vehicles at the start of an ERP Charge Zone on an arterial road. It indicates that vehicles are entering an ERP Charge Zone.

[S 291/2026 wef 15/05/2026]

[S 91/2026 wef 09/03/2026]

DIAGRAM 163(b)

THE SCHEDULE — *continued*




SIZE:

900mm X 900mm

This sign is placed facing approaching vehicles at the start of an ERP Charge Zone on an expressway. It indicates that vehicles are entering an ERP Charge Zone.

[S 91/2026 wef 09/03/2026]

DIAGRAM 163(c)



SIZE:


600mm X 600mm

This sign is placed facing approaching vehicles at the start of an ERP Charge Zone on an arterial road. It indicates that vehicles are entering an ERP Charge Zone.

[S 91/2026 wef 09/03/2026]

DIAGRAM 163(d)

THE SCHEDULE — *continued*




This sign is placed facing approaching vehicles at the start of an ERP Charge Zone on an expressway. It indicates that vehicles are entering an ERP Charge Zone.


[S 291/2026 wef 15/05/2026]

[S 91/2026 wef 09/03/2026]

DIAGRAM 163A(a)




This marking is painted at the start of an ERP Charge Zone on each lane of an

THE SCHEDULE — *continued*

This marking is painted at the start of an ERP Charge Zone on each lane of an arterial road or expressway. It indicates that vehicles on the lane with the marking are entering an ERP Charge Zone.

[S 291/2026 wef 15/05/2026]

[S 91/2026 wef 09/03/2026]

DIAGRAM 164

END OF SCHOOL ZONE


THE SCHEDULE — *continued*

This sign is placed at the end of a demarcated school zone.
It indicates that the section of the road before is near a school.

[S 690/2025 wef 01/01/2026]

[S 782/2013 wef 01/01/2014]

DIAGRAM 165



END OF SILVER ZONE

This sign is placed at the end of a demarcated silver zone. It indicates that elderly pedestrians are likely to be encountered in the section of road before.

DIAGRAM 165A(a)

THE SCHEDULE — *continued*




END OF “FRIENDLY STREETS”

This sign is placed at the end of a zone demarcated as “Friendly Streets”.

[S 367/2024 wef 01/05/2024]

DIAGRAM 165A(b)




END OF “FRIENDLY STREETS”

This sign is placed at the end of a zone demarcated as “Friendly Streets”.

[S 367/2024 wef 01/05/2024]

DIAGRAM 166


THE SCHEDULE — *continued*



Markings indicating a full-day bicycle lane.

[S 803/2022 wef 16/10/2022]

DIAGRAM 167(a)




A full-day bicycle lane at a signalised intersection.

[S 803/2022 wef 16/10/2022]

DIAGRAM 167(b)

THE SCHEDULE — *continued*



A full-day bicycle lane at a bus stop.

[S 803/2022 wef 16/10/2022]

FULL-DAY BICYCLE LANES AT UNCONTROLLED JUNCTIONS OR OPENINGS

DIAGRAM 168(a)

[S 803/2022 wef 16/10/2022]




DIAGRAM 168(b)




DIAGRAM 168(c)

THE SCHEDULE — continued




DIAGRAM 169



This sign indicates that cyclists are likely to be encountered in the section of road ahead, and that motorists should slow down.

DIAGRAM 170(a)

THE SCHEDULE — *continued*

This sign indicates the start of a full-day bicycle lane.

[S 803/2022 wef 16/10/2022]

DIAGRAM 170(b)


THE SCHEDULE — *continued*



This sign indicates the end of a full-day bicycle lane.

DIAGRAM 171


THE SCHEDULE — *continued*



Markings indicating a part-day bicycle lane.

DIAGRAM 172

THE SCHEDULE — *continued*



A part-day bicycle lane at a signalised intersection.

PART-DAY BICYCLE LANES AT BUS STOPS

DIAGRAM 173(a)




DIAGRAM 173(b)





DIAGRAM 174


THE SCHEDULE — continued



This sign indicates the end of a part-day bicycle lane.


DIAGRAM 176(a)

THE SCHEDULE — *continued*



This sign indicates that there is a bus lane camera in the vicinity and that vehicles must only be driven or remain on a bus lane when permitted or face the penalty specified in the sign.


DIAGRAM 176(b)



This sign indicates that there is a bus lane camera in the vicinity and that vehicles must only be driven or remain on a bus lane when permitted.

DIAGRAM 177(a)

THE SCHEDULE — *continued*



This sign indicates that there is a parking enforcement camera in the vicinity and that vehicles must only be parked when permitted or face the penalty specified in the sign.

DIAGRAM 177(b)



THE SCHEDULE — *continued*

This sign indicates that there is a parking enforcement camera in the vicinity and that vehicles must only be parked when permitted.

[S 748/2024 wef 01/10/2024]

[S 803/2022 wef 16/10/2022]

[S 172/2017 wef 22/04/2017]

[S 670/2014 wef 01/10/2014]

[S 276/2018 wef 05/05/2018]

*[G.N. Nos. S 501/91; S 442/92; S 540/93; S 341/94;
S 466/94; S 48/95; S 61/95; S 192/95; S 205/95; S 229/95;
S 538/95; S 171/96; S 319/96; S 196/97; S 223/97;
S 482/97; S 179/98; S 461/98; S 636/98; S 191/99]*

LEGISLATIVE HISTORY
ROAD TRAFFIC (TRAFFIC SIGNS) RULES
(CHAPTER 276, R 33)

This Legislative History is provided for the convenience of users of the Road Traffic (Traffic Signs) Rules. It is not part of these Rules.

1. G. N. No. S 501/1991 — Road Traffic (Traffic Signs) Rules 1991

Date of commencement : 15 November 1991

2. 1990 Revised Edition — Road Traffic (Traffic Signs) Rules

Date of operation : 25 March 1992

3. G. N. No. S 442/1992 — Road Traffic (Traffic Signs) (Amendment) Rules 1992

Date of commencement : 23 October 1992

4. G. N. No. S 540/1993 — Road Traffic (Traffic Signs) (Amendment) Rules 1993

Date of commencement : 3 January 1994

5. G. N. No. S 341/1994 — Road Traffic (Traffic Signs) (Amendment) Rules 1994

Date of commencement : 9 September 1994

6. G. N. No. S 466/1994 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 1994

Date of commencement : 15 December 1994

7. G. N. No. S 48/1995 — Road Traffic (Traffic Signs) (Amendment) Rules 1995

Date of commencement : 11 February 1995

8. G. N. No. S 61/1995 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 1995

Date of commencement : 18 February 1995

9. G. N. No. S 192/1995 — Road Traffic (Traffic Signs) (Amendment No. 3) Rules 1995

Date of commencement : 24 April 1995

10. G. N. No. S 205/1995 — Road Traffic (Traffic Signs) (Amendment No. 4) Rules 1995

Date of commencement : 2 May 1995

11. G. N. No. S 229/1995 — Road Traffic (Traffic Signs) (Amendment No. 5) Rules 1995

Date of commencement : 1 June 1995

12. G. N. No. S 538/1995 — Road Traffic (Traffic Signs) (Amendment No. 6) Rules 1995

Date of commencement : 1 December 1995

13. G. N. No. S 171/1996 — Road Traffic (Traffic Signs) (Amendment) Rules 1996

Date of commencement : 19 April 1996

14. G. N. No. S 319/1996 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 1996

Date of commencement : 19 July 1996

15. G. N. No. S 196/1997 — Road Traffic (Traffic Signs) (Amendment) Rules 1997

Date of commencement : 16 April 1997

16. G. N. No. S 223/1997 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 1997

Date of commencement : 5 May 1997

17. G. N. No. S 482/1997 — Road Traffic (Traffic Signs) (Amendment No. 3) Rules 1997

Date of commencement : 31 October 1997

18. G. N. No. S 179/1998 — Road Traffic (Traffic Signs) (Amendment) Rules 1998

Date of commencement : 1 April 1998

19. G. N. No. S 461/1998 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 1998

Date of commencement : 1 September 1998

20. G. N. No. S 636/1998 — Road Traffic (Traffic Signs) (Amendment No. 3) Rules 1998

Date of commencement : 1 January 1999

21. G. N. No. S 191/1999 — Road Traffic (Traffic Signs) (Amendment) Rules 1999

Date of commencement : 14 April 1999

22. 1999 Revised Edition — Road Traffic (Traffic Signs) Rules

Date of operation : 30 September 1999

23. G. N. No. S 13/2000 — Road Traffic (Traffic Signs) (Amendment) Rules 2000

Date of commencement : 14 January 2000

24. G. N. No. S 83/2000 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 2000

Date of commencement : 1 March 2000

25. G. N. No. S 375/2001 — Road Traffic (Traffic Signs) (Amendment) Rules 2001

Date of commencement : 3 August 2001

26. G. N. No. S 549/2001 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 2001

Date of commencement : 1 November 2001

27. G. N. No. S 334/2003 — Road Traffic (Traffic Signs) (Amendment) Rules 2003

Date of commencement : 14 July 2003

28. G. N. No. S 3/2005 — Road Traffic (Traffic Signs) (Amendment) Rules 2005

Date of commencement : 3 January 2005

29. G. N. No. S 572/2005 — Road Traffic (Traffic Signs) (Amendment No. 2) Rules 2005

Date of commencement : 1 September 2005

30. G. N. No. S 577/2005 — Road Traffic (Traffic Signs) (Amendment No. 3) Rules 2005

Date of commencement : 5 September 2005

31. G. N. No. S 639/2005 — Road Traffic (Traffic Signs) (Amendment No. 4) Rules 2005

Date of commencement : 3 October 2005

32. G. N. No. S 134/2007 — Road Traffic (Traffic Signs) (Amendment) Rules 2007

Date of commencement : 1 April 2007

**33. G. N. No. S 651/2008 — Road Traffic (Traffic Signs) (Amendment)
Rules 2008**

Date of commencement : 20 December 2008

**34. G. N. No. S 257/2009 — Road Traffic (Traffic Signs) (Amendment)
Rules 2009**

Date of commencement : 8 June 2009

**35. G. N. No. S 165/2011 — Road Traffic (Traffic Signs) (Amendment)
Rules 2011**

Date of commencement : 29 March 2011

**36. G. N. No. S 538/2011 — Road Traffic (Traffic Signs) (Amendment No. 2)
Rules 2011**

Date of commencement : 21 September 2011

**37. G. N. No. S 814/2013 — Road Traffic (Traffic Signs) (Amendment No. 2)
Rules 2013**

Date of commencement : 29 December 2013

**38. G. N. No. S 782/2013 — Road Traffic (Traffic Signs) (Amendment)
Rules 2013**

Date of commencement : 1 January 2014

**39. G. N. No. S 670/2014 — Road Traffic (Traffic Signs) (Amendment)
Rules 2014**

Date of commencement : 1 October 2014

**40. G.N. No. S 114/2016 — Road Traffic (Traffic Signs) (Amendment)
Rules 2016**

Date of commencement : 21 March 2016

**41. G.N. No. S 676/2016 — Road Traffic (Traffic Signs) (Amendment No. 2)
Rules 2016**

Date of commencement : 1 January 2017

**42. G.N. No. S 172/2017 — Road Traffic (Traffic Signs) (Amendment)
Rules 2017**

Date of commencement : 22 April 2017

**43. G.N. No. S 189/2017 — Road Traffic (Traffic Signs) (Amendment No. 2)
Rules 2017**

Date of commencement : 28 April 2017

**44. G.N. No. S 158/2018 — Road Traffic (Traffic Signs) (Amendment)
Rules 2018**

Date of commencement : 1 April 2018

**45. G.N. No. S 276/2018 — Road Traffic (Traffic Signs) (Amendment No. 2)
Rules 2018**

Date of commencement : 5 May 2018

**46. G.N. No. S 95/2020 — Road Traffic (Traffic Signs) (Amendment)
Rules 2020**

Date of commencement : 1 March 2020

**47. G.N. No. S 1056/2021 — Road Traffic (Traffic Signs) (Amendment)
Rules 2021**

Date of commencement : 3 January 2022

**48. G.N. No. S 803/2022 — Road Traffic (Traffic Signs) (Amendment)
Rules 2022**

Date of commencement : 16 October 2022

**49. G.N. No. S 170/2024 — Road Traffic (Traffic Signs) (Amendment)
Rules 2024**

Date of commencement : 1 March 2024

**50. G.N. No. S 367/2024 — Road Traffic (Traffic Signs) (Amendment No. 2)
Rules 2024**

Date of commencement : 1 May 2024

**51. G.N. No. S 748/2024 — Road Traffic (Traffic Signs) (Amendment No. 3)
Rules 2024**

Date of commencement : 1 October 2024

**52. G.N. No. S 690/2025 — Road Traffic (Traffic Signs) (Amendment)
Rules 2025**

Date of commencement : 1 January 2026

**53. G.N. No. S 883/2025 — Road Traffic (Traffic Signs) (Amendment No. 2)
Rules 2025**

Commencement : 1 January 2026

**54. G.N. No. S 91/2026 — Road Traffic (Traffic Signs) (Amendment)
Rules 2026**

Date of commencement : 9 March 2026

**55. G.N. No. S 227/2026 — Road Traffic (Traffic Signs) (Amendment No. 2)
Rules 2026**

Date of commencement : 20 April 2026

**56. G.N. No. S 291/2026 — Road Traffic (Traffic Signs) (Amendment No. 3)
Rules 2026**

Date of commencement : 15 May 2026